ZITHA TECH SPECIALTY CABLES (Pty) Ltd

How to configure the power supply for the power distribution box



Overview

Power Supply Box VideosPTC Auto Reset FusePower Supply Box Installation GuidesWiring DiagramsRelated ArticlesRelated Video Surveillance EquipmentWiring a CCTV Camera to Power Supply Box with Premade Siamese CableThis video shows installers how to connect a CCTV camera to a 12V DC power supply box using premade Siamese security camera cables.

Key Takeaways

To configure the power supply in a distribution box, connect the main input to the main breaker, arrange branch circuit breakers according to load, ensure proper wire sizing and color coding, and perform safety checks before powering on.Step 1: Prepare the Distribution Box

Ensure the distribution box is securely installed in a dry, accessible location with proper ventilation. Check that the enclosure meets the required IP or NEMA rating for protection against dust and moisture, and that it is made of durable material suitable for the environment (steel for industrial, plastic for indoor use) .

Step 2: Select and Arrange Circuit Breakers
• Main Breaker: Install a double-pole MCB as the main switch to handle the incoming power supply. For domestic single-phase systems, a 63A MCB is commonly used .

• Branch Breakers: Use single-pole MCBs for individual circuits such as lighting and sockets. For high-power appliances, double-pole MCBs may be used.

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved

• Arrange breakers from left to right, leaving reserved space on the right for future expansion .
Step 3: Wire the Power Supply
• Incoming Supply: Connect the phase (live) and neutral wires from the main supply to the main breaker.

• Branch Connections: Connect each branch circuit to its respective breaker. Wiring from the main breaker to branch breakers typically runs on the left side of the box, while outgoing wires to loads exit on the right .

• Wire Color Coding: Use standard colors—blue for neutral, yellow for phase A, green for phase B, and red for phase C. Ensure wire gauge matches the load (e.g., 2.5mm² for lighting and sockets, 4mm² for air conditioning) .
Step 4: Install Protective Devices

Include RCCBs or RCDs to protect against earth faults and leakage currents. Each circuit should have its own protection device to prevent overloads and short circuits .

Step 5: Organize and Label
• Bind wires neatly with plastic ties, maintaining uniform spacing to avoid tangling.

• Clearly mark AC/DC circuits and voltage levels to prevent confusion during maintenance .

• Label each breaker according to the area or appliance it serves for easy identification.
Step 6: Safety Inspection

Before powering on, perform a thorough inspection:

• Check all connections for tightness and correct polarity.

• Use a multimeter to verify voltage and continuity.

• Ensure no exposed wires or potential short circuits exist . Following these steps ensures a safe, organized, and compliant distribution box setup, reducing the risk of electrical hazards and facilitating future maintenance or upgrades.

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved

Article Content

CCTV Power Supply Box, Power Distribution Box for CCTV

Power Supply Box VideosPTC Auto Reset FusePower Supply Box Installation GuidesWiring DiagramsRelated ArticlesRelated Video Surveillance EquipmentWiring a CCTV Camera to Power Supply Box with Premade Siamese CableThis video shows installers how to connect a CCTV camera to a 12V DC power supply box using premade Siamese security camera cables. The process is exactly the same for 24VAC power supply boxes, except that the cable polarity does not matter with alternating current (+ and - does not matter See more on cctvcamerapros

Searches you might like

3 phase power distribution boxelectrical distribution boxpower distribution panelcam lock power distribution boxsanyodenki

Power Distribution Box - SANUPS by SANYO DENKI

To use the Power Distribution Box correctly and safely, read this manual before using the product. For details on UPS installation

Related Video Reference

This video was associated with the source search result. Verify technical details against current product documentation and project requirements.

Contact Us

Continue your research online:

Website: https://zithatech.co.za
Technical inquiry: https://zithatech.co.za/contact.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved